



Università degli Studi Mediterranea di Reggio Calabria
Archivio Istituzionale dei prodotti della ricerca

INTEGRATED METHODOLOGY FOR URBAN FLOOD RISK MITIGATION IN CITTANOVA, ITALY

This is the peer reviewed version of the following article:

Original

INTEGRATED METHODOLOGY FOR URBAN FLOOD RISK MITIGATION IN CITTANOVA, ITALY / Scionti, F., Miguez, M.g., Barbaro, G., DE SOUSA, M.m., Giandomenico, F., Canale, C.. - In: JOURNAL OF WATER RESOURCES PLANNING AND MANAGEMENT. - ISSN 0733-9496. - 144:10(2018), pp. 1-10. [10.1061/(ASCE)WR.1943-5452.0000985]

Availability:

This version is available at: <https://hdl.handle.net/20.500.12318/1104> since: 2020-04-14T00:16:06Z

Published

DOI: [http://doi.org/10.1061/\(ASCE\)WR.1943-5452.0000985](http://doi.org/10.1061/(ASCE)WR.1943-5452.0000985)

The final published version is available online at: [https://ascelibrary.org/doi/10.1061/\(ASCE\)WR.1943-](https://ascelibrary.org/doi/10.1061/(ASCE)WR.1943-)

Terms of use:

The terms and conditions for the reuse of this version of the manuscript are specified in the publishing policy. For all terms of use and more information see the publisher's website

Publisher copyright

This item was downloaded from IRIS Università Mediterranea di Reggio Calabria (<https://iris.unirc.it/>) When citing, please refer to the published version.

(Article begins on next page)

This is the peer reviewed version of the following
article:

Integrated Methodology for Urban Flood Risk Mitigation in Cittanova, Italy

Fabio Scionti, Ph.D.; Marcelo Gomes Miguez, D.Sc.; Giuseppe Barbaro, Ph.D.; Matheus Martins De Sousa, D.Sc.; Giandomenico Foti, Ph.D.; and Caterina Canale, Dr.Eng.

Journal of Water Resources Planning and Management, Vol. 144, Issue 10 (October 2018)

[https://doi.org/10.1061/\(ASCE\)WR.1943-5452.0000985](https://doi.org/10.1061/(ASCE)WR.1943-5452.0000985)

which has been published in final version:

<https://ascelibrary.org/doi/pdf/10.1061/%28ASCE%29WR.1943-5452.0000985?download=true>

The terms and conditions for the reuse of this version of the manuscript are specified in the publishing policy. for all terms of use and more information see the publisher's website.

Journal of Water Resources Planning and Management

An Integrated Methodology for urban flood risk mitigation: the case study of Cittanova (Italy)

--Manuscript Draft--

Manuscript Number:	WRENG-2813R3
Full Title:	An Integrated Methodology for urban flood risk mitigation: the case study of Cittanova (Italy)
Manuscript Region of Origin:	ITALY
Article Type:	Case Study
Funding Information:	
Abstract:	Urban growth usually aggravates flooding problems, disrupting city life and requiring engineering works to ensure safety conditions to lower lying city areas. Traditionally, canalisation works were the preferred choice for flood mitigation. However, increased city growth limits the effectiveness of this approach due to the lack of free spaces and local canalisation practices tend to transfer flooding downstream in a non-sustainable way. In the last eighty years, the town of Cittanova, in the province of Reggio Calabria (Italy), has been subjected to several flooding events related to river overflows or storm drain failures causing significant damages to mobility, households and even to public safety. This paper focuses on the Forio Creek, which is a tributary of the Vacale River and runs through the city. The study was carried out using mathematical tools within a conceptual framework with the aim of mapping floods to prevent damage to the city and avoid future losses, thus reducing risks. MODCEL was the hydrodynamic model used to map urban floods and to support the use of the Flood Risk Index (FRI), which is a quantitative multi-criteria tool relating flood levels to socio-economic losses. Both the MODCEL and the FRI were previously available, but their combined use and the final integrated analyses carried in this paper introduce a simple and quantifiable flood risk procedure to identify the present flood risks and to foresee future scenarios whilst supporting alternative design and prioritizing flood control choices. This framework was applied to Cittanova and validated by practical observations.
Corresponding Author:	Giuseppe Barbaro Universita degli Studi Mediterranea di Reggio Calabria Reggio Calabria, ITALY
Corresponding Author E-Mail:	giuseppe.barbaro@unirc.it
Order of Authors:	Fabio Scionti Marcelo Gomes Miguez Giuseppe Barbaro Matheus Martins De Sousa Giandomenico Foti Caterina Canale
Suggested Reviewers:	Francesco Laio francesco.laio@polito.it Expert in hydrology, water resources assessment, environmental modelling, and statistics Dragan Savic D.Savic@exeter.ac.uk Expert in development and application of decision-support systems, simulation and optimization models to improve understanding and provide solutions to water engineering problems, and management of urban water systems. Kevin E. Lansey lansey@email.arizona.edu Expert in water resources problems with emphasis on water distribution and systems analysis.

Opposed Reviewers:	
Additional Information:	
Question	Response
If yes, please indicate which figures in the comments box. as follow-up to "The flat fee for including color figures in print is \$800, regardless of the number of color figures. There is no fee for online only color figures. If you decide to not print figures in color, please ensure that the color figures will also make sense when printed in black-and-white, and remove any reference to color in the text. Only one file is accepted for each figure. Do you intend to pay to include color figures in print? If yes, please indicate which figures in the comments box. "	Figure 3 Figure 5 Figure 6 Figure 7 Figure 8 Figure 9 Figure 10 Tab2-ALT.0 Tab2-ALT.1 Tab2-ALT.2 Tab2-ALT.3 Tab2-ALT.4 Tab2-ALT.5 Tab2-ALT.6 Tab2-ALT.7 Tab2-ALT.8
Authors are required to attain permission to re-use content, figures, tables, charts, maps, and photographs for which the authors do not hold copyright. Figures created by the authors but previously published under copyright elsewhere may require permission. For more information see http://ascelibrary.org/doi/abs/10.1061/9780784479018.ch03. All permissions must be uploaded as a permission file in PDF format. Are there any required permissions that have not yet been secured? If yes, please explain in the comment box.	No
ASCE does not review manuscripts that are being considered elsewhere to include other ASCE Journals and all conference proceedings. Is the article or parts of it being considered for any other publication? If your answer is yes, please explain in the comments box below.	No
Is this article or parts of it already published in print or online in any language? ASCE does not review content already published (see next questions for conference papers and posted theses/dissertations). If your answer is yes, please explain in the comments box below.	No
Has this paper or parts of it been published as a conference proceeding? A conference proceeding may be reviewed for publication only if it has been significantly revised and contains 50% new content. Any content overlap should be reworded and/or properly referenced. If	No

your answer is yes, please explain in the comments box below and be prepared to provide the conference paper.	
ASCE allows submissions of papers that are based on theses and dissertations so long as the paper has been modified to fit the journal page limits, format, and tailored for the audience. ASCE will consider such papers even if the thesis or dissertation has been posted online provided that the degree-granting institution requires that the thesis or dissertation be posted. Is this paper a derivative of a thesis or dissertation posted or about to be posted on the Internet? If yes, please provide the URL or DOI permalink in the comment box below.	No
Each submission to ASCE must stand on its own and represent significant new information, which may include disproving the work of others. While it is acceptable to build upon one's own work or replicate other's work, it is not appropriate to fragment the research to maximize the number of manuscripts or to submit papers that represent very small incremental changes. ASCE may use tools such as CrossCheck, Duplicate Submission Checks, and Google Scholar to verify that submissions are novel. Does the manuscript constitute incremental work (i.e. restating raw data, models, or conclusions from a previously published study)?	No
Authors are expected to present their papers within the page limitations described in Publishing in ASCE Journals: A Guide for Authors. Technical papers and Case Studies must not exceed 30 double-spaced manuscript pages, including all figures and tables. Technical notes must not exceed 7 double-spaced manuscript pages. Papers that exceed the limits must be justified. Grossly over-length papers may be returned without review. Does this paper exceed the ASCE length limitations? If yes, please provide justification in the comments box below.	No
All authors listed on the manuscript must have contributed to the study and must approve the current version of the manuscript. Are there any authors on the paper that do not meet these criteria? If the answer is yes, please explain in the	No

comments.	
Was this paper previously declined or withdrawn from this or another ASCE journal? If so, please provide the previous manuscript number and explain what you have changed in this current version in the comments box below. You may upload a separate response to reviewers if your comments are extensive.	No
Companion manuscripts are discouraged as all papers published must be able to stand on their own. Justification must be provided to the editor if an author feels as though the work must be presented in two parts and published simultaneously. There is no guarantee that companions will be reviewed by the same reviewers, which complicates the review process, increases the risk for rejection and potentially lengthens the review time. If this is a companion paper, please indicate the part number and provide the title, authors and manuscript number (if available) for the companion papers along with your detailed justification for the editor in the comments box below. If there is no justification provided, or if there is insufficient justification, the papers will be returned without review.	This isn't a companion paper
If this manuscript is intended as part of a Special Issue or Collection, please provide the Special Collection title and name of the guest editor in the comments box below.	This isn't a Special Issue or Collection
Recognizing that science and engineering are best served when data are made available during the review and discussion of manuscripts and journal articles, and to allow others to replicate and build on work published in ASCE journals, all reasonable requests by reviewers for materials, data, and associated protocols must be fulfilled. If you are restricted from sharing your data and materials, please explain below.	I haven't restricted from sharing data and materials
Papers published in ASCE Journals must make a contribution to the core body of knowledge and to the advancement of the field. Authors must consider how their new knowledge and/or innovations add value to the state of the art and/or state of the practice. Please outline the specific contributions of this research in the comments box.	This paper suggests a strategy of staggering the alternative measures in time shall be developed, matching them with the investment capacity.

The flat fee for including color figures in print is \$800, regardless of the number of color figures. There is no fee for online only color figures. If you decide to not print figures in color, please ensure that the color figures will also make sense when printed in black-and-white, and remove any reference to color in the text. Only one file is accepted for each figure. Do you intend to pay to include color figures in print? If yes, please indicate which figures in the comments box.	No
If there is anything else you wish to communicate to the editor of the journal, please do so in this box.	No

An Integrated Methodology for urban flood risk mitigation: the case study of Cittanova (Italy)

Fabio Scionti¹; Marcelo Gomes Miguez²; Giuseppe Barbaro³; Matheus Martins De Sousa⁴;
Giandomenico Foti⁵; Caterina Canale⁶

¹ Ph.D., Mediterranean University, DICEAM Department, Via Graziella località Feo di Vito, 89122
Reggio Calabria (Italy). E-mail: fascipama@tiscali.it

² Associate Professor, Universidade Federal do Rio de Janeiro-UFRJ, Escola Politécnica-POLI &
Civil Engineering Program-PEC/COPPE Av. Athos da Silveira Ramos, 149, CT, I-206 Cidade
Universitária Rio de Janeiro - RJ - Brasil. E-mail: marcelomiguez@poli.ufrj.br

³ Associate Professor, Mediterranean University, DICEAM Department, Via Graziella località Feo
di Vito, 89122 Reggio Calabria, Italy (corresponding author). E-mail: giuseppe.barbaro@unirc.it

⁴ D.Sc., AquaFluxus-Consultoria Ambiental em Recursos Hídricos Rua Paulo Emídio Barbosa,
485, 1A, CE-TIC, 106 Cidade Universitária - Parque Tecnológico da UFRJ Rio de Janeiro - RJ –
Brasil. E-mail: matheus@aquafloxos.com.br

⁵ Ph.D., Mediterranean University, DICEAM Department, Via Graziella località Feo di Vito, 89122
Reggio Calabria (Italy). E-mail: giandomenico.foti@unirc.it

⁶ Dr.Eng., Mediterranean University, DICEAM Department, Via Graziella località Feo di Vito,
89122 Reggio Calabria (Italy). E-mail: kcanale@libero.it

Abstract

Urban growth usually aggravates flooding problems, disrupting city life and requiring engineering
works to ensure safety conditions to lower lying city areas. Traditionally, canalisation works were
the preferred choice for flood mitigation. However, increased city growth limits the effectiveness of
this approach due to the lack of free spaces and local canalisation practices tend to transfer flooding
downstream in a non-sustainable way. In the last eighty years, the town of Cittanova, in the

25 province of Reggio Calabria (Italy), has been subjected to several flooding events related to river
26 overflows or storm drain failures causing significant damages to mobility, households and even to
27 public safety. This paper focuses on the Forio Creek, which is a tributary of the Vacale River and
28 runs through the city. The study was carried out using mathematical tools within a conceptual
29 framework with the aim of mapping floods to prevent damage to the city and avoid future losses,
30 thus reducing risks. MODCEL was the hydrodynamic model used to map urban floods and to
31 support the use of the Flood Risk Index (FRI), which is a quantitative multi-criteria tool relating
32 flood levels to socio-economic losses. Both the MODCEL and the FRI were previously available,
33 but their combined use and the final integrated analyses carried in this paper introduce a simple and
34 quantifiable flood risk procedure to identify the present flood risks and to foresee future scenarios
35 whilst supporting alternative design and prioritizing flood control choices. This framework was
36 applied to Cittanova and validated by practical observations.

37 **Keywords:** Urban floods; Flood risk management; Planning and design; MODCEL; Multi-
38 criteria index; Cittanova.

40 **Introduction**

41 A city's interaction with its natural watershed leads to typical urban structures acting
42 hydraulically, complementing the drainage system functions, when this system fails in its primary
43 task of safely conveying rainwaters. In this situation, for example, streets may act as channels,
44 squares and buildings may act as undesired reservoirs, walls may play the role of weirs, and so on.
45 The land shapes and varied structures of the built environment thus interact to diversify possible
46 flow patterns (Miguez *et al.*, 2011), increasing the complexity of the phenomenon. Therefore, the
47 inherent difficulties in predicting the dynamics of water flowing in complex urban environment
48 systems lead to the use of mathematical models.

49 The development of models describing the rainfall-runoff relation over a catchment area
50 has been the prime focus of hydrological research for many decades. Hydrodynamic models are
51 also commonly used to route floods in watersheds. The answers provided by these models,
52 however, are just the first step in the task of risk analysis.

53 Risk assessment involves two distinct components: the probability of an event; and the
54 magnitude of consequences produced by that event (Mcanally *et al.*, 2013). It is necessary to know
55 what vulnerabilities arise from the urban system and what damages and losses may occur when the
56 socio-economic elements of the system are exposed to hazard. These expected losses can be
57 explained by:

- 58 (1) the exposure of the system elements,
59 (2) the susceptibility to suffer damage related to these exposed elements, and
60 (3) their ability to react and return to their reference state, which is associated with the
61 concept of resilience (see for instance Andersson, 2006; Godschalk, 2003; Jha *et al.*, 2012; Prasad
62 *et al.*, 2009; Vale & Campanella, 2005; Wang & Blackmore, 2009; Miguez & Veról, 2016;
63 Connelly *et al.*, 2016; Hossain *et al.*, 2017).

64 Rainfall is the natural source event that triggers a flood hazard. However, the flood
65 characteristics and severity depend on how the watershed converts rainfall into runoff, and the
66 consequent peak discharges conveyed. Flood control measures are therefore required to enhance the
67 resilience of the urban environment to adapt to extreme rainfall events. In this context, the
68 opportunities offered by the open spaces system and landscaping to re-interpret and update urban
69 water systems are considered (Blackmore and Plant, 2008). Reducing flood risk is a task that may
70 be accomplished by minimising the results of the rainfall-runoff transformation with on-source
71 control measures, and redistributing the flood flows in space and time by using storage and
72 infiltration structures to fulfil this aim (Burian and Edwards, 2002). Drainage design procedures are
73 evolving from a single focus on the primary services that ensure public health, such as flood
74 mitigation, towards a more integrated use of urban waters within the city itself (Walsh *et al.*, 2016).
75 These new trends in urban drainage design point to systemic solutions for flood control. Distributed
76 measures are used to restore flow patterns in the watershed, simulating hydrologic conditions that
77 happened prior to urbanisation.

78 The related literature shows the development of a set of concepts that stress the evolution
79 of a more holistic approach (Fletcher *et al.*, 2015). It is possible to mention some examples that
80 highlight this conceptual evolution as follows: Low Impact Development-LID (US EPA, 2000;
81 Ahiablame *et al.*, 2012; Carlson *et al.*, 2014; Ahiablame, 2016; Giacomoni & Joseph, 2017);
82 Sustainable Urban Drainage Systems-SUDS (Woods-Ballard *et al.* 2007, Chocat *et al.*, 2007,
83 Barbosa *et al.*, 2012; Miguez *et al.*, 2012; Mguni *et al.*, 2016); and Water Sensitive Cities (Argue,
84 J.R., ed., 2004; Wong and Brown, 2008; Johnstone, 2011, Brown *et al.*, 2016). In general, these
85 approaches integrate urban water management needs with city infrastructure functions, and try to
86 accommodate the urban waters within the urban landscape in a positive way, by increasing
87 biodiversity, providing recreational uses and revitalizing both the built environment and the river
88 corridors.

89 Rainwaters can additionally be harvested and offered as a valuable resource. Kim and Han
90 (2007) for example, proposed the Rainfall-Storage-Drain (RSD) model to support the design of
91 rainwater harvesting reservoirs integrated with the drainage system demands. These relatively small
92 reservoirs distributed in the urban tissue and acting to lower the impact development on hydrology,
93 were able to reduce peak discharges from 25% to 75% when compared to the original discharge
94 values (Avila *et al.*, 2016).

95 However, when investment capacity is limited, it is necessary to identify which are the
96 most fragile areas in terms of negative flooding results, and where the protection offered will be
97 more effective against socio-economic losses. This consideration points to system vulnerabilities.
98 The association of multi-objective tools with hydrodynamic models can provide useful support to
99 decision makers in choosing among feasible alternatives, with optimal cost-quality ratios (Barreto *et*
100 *al.*, 2010). Although different academic studies were already developed following this new trend,
101 daily practices in urban water management show that most cities are still focused only on mitigating
102 inundation.

103 In this work, a hydrodynamic model is combined with a quantitative multi-criteria flood
104 risk assessment. The model of choice was MODCEL (Mascarenhas and Miguez., 2002;
105 Mascarenhas *et al.*, 2005; Miguez *et al.*, 2011). This is a *quasi*-2D model, which is capable to
106 represent city patterns and a complex flow net, using simple topographic data. On the other hand,
107 the Flood Risk Index (FRI) uses a multi-criteria approach to target complex socioeconomic
108 variables, also in a simple way, using the available information, which is easily gathered from
109 census databases or from local interviews. The proposed framework tries to keep the flood and risk
110 modelling simple and representative to allow for and favour a wide practical application. This
111 approach was applied in a case study in the city of Cittanova, in the province of Reggio Calabria
112 (Italy). This city is located in the Petrace river basin, near its tributaries Serra and Vacale. The city
113 has been flooded several times in the recent past, and its main problem is related to the urban storm

114 water management. Therefore, superficial flows play an important role in the city flooding. More
115 specifically, the objectives drawn for this study may be summarised as follows:

- 116 ▪ Draw hazard maps for the urban centre of Cittanova, identifying areas of high, medium and
117 low probability of flooding.
- 118 ▪ Track potential vulnerability maps, considering the possible damages to each flooded area
119 (depending on number of inhabitants, strategic facilities, environmental goods, etc.).
- 120 ▪ Propose and test innovative solutions to restore natural water cycle functions that were lost
121 due to the urbanisation process. This approach also seeks to support a sustainable urban
122 storm water management, integrated with land use control, and ultimately seeking
123 recommendations for a safer future development.

124 The novelty of this approach does not fall in the individual tools used, but rather on the composite
125 framework that is proposed. The joint combination of a hydrodynamic model, with a quantitative
126 flood risk index to support flood control design and land use planning, involving the participation of
127 the local population and public managers, provided a useful procedure to assess different risk
128 scenarios, to evaluate alternative choices for flood control, and to properly define the landscape
129 planning and land use control guidelines for Cittanova.

130 **Mathematical Hydrodynamic Modelling**

131 Many mathematical models tend to reduce the time-space interaction to a single result in a
132 specific section (see, for instance, HEC-HMS - Scharffengerg and Fleming, 2010). Other models
133 tend to concentrate on water systems management or on the behaviour of hydraulic structures, for
134 example, SWMM (Rossman, 2015). Some approaches use one-dimensional (1D) relations focusing
135 on the drainage network, others represent two-dimensional (2D) flood plain flows. However, the
136 modelling of urban floods should be carried out with a mixed approach considering runoff
137 generation, consequent superficial flows, storm drains and river flows. Flows in flood plains may
138 occur in various directions and may be influenced by local structures. Therefore, a model capable of

139 fulfilling the requisites for urban floods simulation should preferentially be able to perform rainfall-
140 runoff transformation and to represent the watershed flow patterns in a distributed way, integrating
141 surface flows with the storm drains network.

142 When the superficial flow is governed by urban patterns (interaction with buildings, walls
143 and other structural obstacles), it is difficult to represent the flooding surface with traditional 2D
144 models, because there are in fact several discontinuities in the resulting water surface. On the other
145 hand, 1D models focusing on the drainage system behaviour tend to misrepresent the important
146 superficial processes.

147 Abily *et al.* (2013) modelled a dense and complex industrial site, with above ground
148 structures affecting drainage paths (similar to what happens in the urban landscape) and stressed
149 that models based on 2D equations can face several problems, such as rapid changes in flow regime,
150 small water depths and high gradients, vertical effects in runoff hydrodynamics, and free/
151 surcharged flow in drainage pipes, among others. On the other hand, Leandro *et al.* (2009)
152 discussed the use of 1D/1D and 1D/2D models, observing that 2D models are computationally
153 much more expensive than 1D models, resulting in much greater times of computation.

154 An alternative that combines the simplicity of 1D models and their low computational
155 costs with the details of 2D representation of superficial flows, and also recognises the presence of
156 above ground obstacles, refers to quasi-2D models. This paper uses a mathematical quasi-2D model
157 to simulate urban floods. MODCEL (Mascarenhas and Miguez, 2002; Miguez *et al.*, 2011) is based
158 on the concept of flow cells (Zanobetti *et al.*, 1970) integrating urban land surface and drainage net
159 features. It represents the watershed through a set of homogeneous compartments which interact
160 with each other creating a complex flow net connected by several different and relatively simple
161 hydraulic laws. Although its conception is old, it remains quite useful when physical interpretation
162 is required and an extensive and continuous 2D water surface is not observed in practice (see, for
163 instance, Barbedo *et al.*, 2015; Nardini *et al.*, 2016). The choice of MODCEL to simulate floods in
164 Cittanova is mainly supported by the following case characteristics:

- The main problem refers to storm drain overflows (and not to river overflows), and the observed flooded areas do not define a continuous flow surface—local obstacles are important and flows are driven by urban structures.
- It is important to model flood control alternatives using landscape features, not only focusing on the drainage net – there is little space for storm drain enlargements and a sustainable approach is required, with on-source control measures and multifunctional landscapes capable of storing part of the floods.

The MODCEL Model

MODCEL was built to model the urban surface using a set of homogeneous compartments called flow cells, integrating the catchment area. The compartments interact through cell links representing different hydraulic laws. Each cell also transforms rainfall into run-off using the rational method in a distributed way, due to the spatial coverage provided by the interconnected cells. The mesh of cells composes a hydrodynamic looped model that links surface flow, channel flow and storm drain flow. A vertical link communicates the superficial layer, corresponding to free surface channels and flooded areas, with the underground layer, related to free surface or surcharged flow in storm drains. Figure 1 illustrates the MODCEL schematic representation. A pre-defined set of cell types is available as follows:

- River/channel cells: represent river reaches or open channel reaches, with simple or compound rectangular cross sections. Note that it is a reasonable approach when considering urban drainage.
- Storm drain cells: act as complements to the drainage net, representing underground pipes.
- Urbanized superficial cells: represent free surface flow over urban floodplains – the flow itself occurs through the streets, while open spaces, squares and even buildings work as storage areas. This cell present compound bottom levels, as shown in figure 2.

- Natural superficial cells: they preserve a natural pattern, without buildings. They may have a storage area minor than that of total superficial area (where rainfall occurs), excluding natural elevations from the mass balance.
- Reservoir cells: used to simulate water storage in a temporary pond or reservoir, using a curve for the elevation versus surface area.

The hydrodynamic model uses the conservation law and a set of hydraulic relations. A detailed deduction of the original flow equations may be found on Cunge et.al (1980). The latest version of MODCEL may be found in Miguez *et al.* (2011). The hydraulic links used in this study are listed below:

- River/Channel link – represented by the Saint-Venant dynamic equation.
- Surface flow link – represented by the Saint-Venant dynamic equation without inertia terms.
- Storm drain link – open channel flow represented either by the Saint Venant equation, if free flow occurs, or by the Bernoulli equation, if surcharged flow occurs. The model manages transitions between these two states, checking at each time step.
- Gutter inlet link – This link promotes the interface between surface flow and storm drain cells. When not drowned, this link acts as a weir; otherwise, it acts as an orifice.
- Broad crested weir link.
- Orifice link.
- Reservoir link – This link combines an orifice, as the outlet discharge of a reservoir, with a weir, which can be activated depending on reservoir water levels.

Flood Risk Index (FRI)

The concept of flood risk mitigation (Balica *et al.*, 2009; Woodward *et al.*, 2013) has gained importance in recent decades. However, flood risk assessments face some difficulties due to the subjective nature of its evaluation and due to the large number of factors that interfere with risk. Zonensein (2008) proposed a quantitative multi-criteria index, named Flood Risk Index (FRI), to

214 address these difficulties. This index is able to conjugate sub-indices related both to flood
215 characteristics and to flood consequences over the city's socioeconomic system. FRI was
216 spatialized and conjugated with MODCEL representation, so that each cell was associated with a
217 FRI normalized value ranging from 0 to 100. The indicators selected to represent flood properties
218 include:

- 219 ▪ the maximum water depth, which directly accounts for losses in the buildings, related to
220 both structure and contents,
- 221 ▪ the velocity factor, resulting from the product of the water depth by the flow velocity and
222 accounting for the dragging forces that can carry people, vehicles or even buildings, and
- 223 ▪ the duration factor, associated with the permanence of the water level above pre-defined
224 thresholds, representing water levels affecting people, traffic and buildings. The time of
225 contact with inundation waters may aggravate losses and affect public health.

226 In addition, indicators for household density, income per capita, traffic hierarchy and
227 inadequate sanitation represent, respectively, the estimated flood consequences over people,
228 structures and their contents, mobility, and public health. A weighted product of two weighted
229 summations, as seen in Equation 1, comprises the formulation of FRI. In order to have the FRI scale
230 ranging from 0 to 100, all of the indicators were normalised. For example, water depths were
231 divided by a reference value which was considered to lead to a total loss for the building contents.
232 The household density was also divided by a reference density, considering the maximum effect in
233 the watershed. In general, a percent reasoning was used.

$$234 \qquad \qquad \qquad FRI = FP^{q_{FP}} \cdot C^{q_C} \qquad (1)$$

235 Where:

- 236 - FRI: Flood Risk Index, ranging from 0 (lowest risk) to 100 (highest risk).
- 237 - FP: sub-index representing a weighted summation of the flood properties for a design rainfall
238 with a certain return period.

- 239 - C: sub-index representing a weighted summation of the consequences of flood.
- 240 - q_{FP} , q_C : weights corresponding to flood properties and consequences, respectively.

241

242 Note that if either sub-index is null or negligible, there must be no risk. On the other hand,
243 the presence of at least one non-zero indicator in each sub-index results in non-negligible risk.
244 Bringing together the views of the institutions and of the managerial class that is responsible for
245 flood risk management in Cittanova, has guided the weights definition. The public managers and
246 the municipality staff also helped in the discussion that defined the classes of risk, as briefly defined
247 below:

- 248 ▪ FRI value between 0 and 25: tolerable risk;
- 249 ▪ FRI value between 25 and 50; manageable risk;
- 250 ▪ FRI value between 50 and 75: medium to high risk – demands intervention;
- 251 ▪ FRI value between 75 and 100: high to very high risk – high priority; demands intervention.

252 **Methodology**

253 Using the tools described above and organizing a set of procedures to join flood control
254 and risk management, the following methodology was proposed and used in this work:

- 255 ▪ The watershed was considered as the basic unit for planning and design purposes.
- 256 ▪ A detailed conceptual diagnosis for the main watershed flooding problems was produced.
- 257 ▪ A spatial analysis provided a broad view of conflicts and potentialities in the considered
258 territory – it is important to highlight from the beginning what you intend to preserve,
259 recover or allow.
- 260 ▪ Flood hazard maps were produced with MODCEL.
- 261 ▪ Natural limits were recognised from the modelling results and the previous analysis.
- 262 ▪ The main socioeconomic variables were mapped.
- 263 ▪ Risk maps were produced combining FRI with MODCEL.

- Design alternatives for reducing risks were tested to better shape urban needs according to the natural limits imposed.

Case study

Study Area and river basin characteristics

The study area consists mainly of the urban area of Cittanova, in the province of Reggio Calabria – Italy (Figure 3). The city is 400 m above mean sea level and 65% of its land is flat. It is located on the plain of Gioia Tauro, in the foot of the Aspromonte Mountains. The Vacale and Serra rivers are the major watercourses in the city area. Both rivers belong to Petrace river basin. However, Forio Creek, which is a tributary of Vacale, is the main river responsible for the Cittanova flooding. Its drainage area covers the centre of the city (2 km²), and the hill east of the city (1.2 km²), to reach 3.2 km². Forio Creek has torrential characteristics, with high bottom slopes and a short time of concentration. A concentration time of 26 minutes was calculated according to the route taken by Forio from its upstream stretches until it reaches the local railway, exiting the city centre. Concrete walls or stone works appear in great parts of the riverbanks, except for the centre of Cittanova, where there are no dykes. The increasing urbanisation process and the consequent canalisation of the watercourse forced the creek to run underground, through 300m of storm drains, in a situation that favours drainage failure and the likelihood of flood hazards (Barbaro *et al.*, 2015).

In 1936, an extraordinary rainfall event of 260 mm devastated the city causing landslides and flooding. City services collapsed. Another great flood occurred in October 1951, producing one death and the collapse of the railway bridge that connects Cittanova and San Mauro. In the following decades the city was hit by several other flood events, but the worst rainfall occurred in November 2011. During that event, 366.4 mm of rainfall disrupted the city. The main roads and the connection with rural areas were unusable. Rainwaters invaded schools, shops and public offices. It was a great disaster, including loss of life. Today, people remember the tragic event with fear and a

289 great feeling of insecurity.

290 A detailed survey of urban area of Cittanova, aiming to identify the characteristics of the
291 territory and the geometry of the storm drains system (manholes, inlet grates etc.), was carried out
292 before starting the mathematical modelling. In parallel to this field activity, a questionnaire
293 prepared by the authors was distributed to a sample of inhabitants. It was structured in three parts,
294 namely: the description of the territory, the description of the buildings and the description of the
295 goods owned by the inhabitants residing there. This questionnaire was used to reliably estimate the
296 economic losses due to the floods.

297 **Hydrological analysis**

298 The watershed physical characteristics, such as topography, urbanisation patterns and land
299 use, as well as the storm drain system characteristics, were used in the hydrologic studies.

300 The hydrological input data was produced using rainfall intensity-duration-frequency
301 curves for different return periods (50, 200 and 500 years). The return period of 50 years was taken
302 as reference for the current studies and the rainfall intensity for this return period may be obtained
303 by Equation 2.

$$304 \quad h_t = 77.088.t^{0.4025} \quad (2)$$

305 Where:

- 306 - h_t : total precipitation in mm.
- 307 - t : rainfall duration in hours.

308 The design rainfall was built considering incremental rainfall blocks of ten minutes each.
309 The duration of ten minutes was considered as the minimal critical time step to evaluate minor
310 drainage behaviour. That is, when considering blocks of ten minutes, the maximum intensity
311 obtained for this duration is the critical rainfall to curbs and inlets in the local scale. On the other
312 hand, completing the total design hyetograph until reaching the concentration time of 30 minutes,

the watershed is also subjected to its critical rainfall event in terms of total volume. Therefore, the total rainfall and the intensity were calculated every 10 minutes, up to 30 minutes, as presented in Table 1. Note that the second block is the result of the total rainfall for 20 minutes minus the total rainfall for the first 10 minutes. Similarly, the third block refers to the total rainfall of 30 minutes minus the total rainfall of 20 minutes. This approach allowed to simulate the critical rainfall intensity in the watershed scale (represented by the average value of the three blocks), as well as the critical rainfall intensity in the local scale (given by the rainfall intensity of the first block). It is important to remind that the resulting hydraulic effects on the watershed responses depend not only on the volume of the hydrograph, but also on its shape. This complementary aspect, however, was not explored in this research.

Hydrodynamic analysis

MODCEL was used to model the urban centre of the city as well as the eastern hills, which directly contribute to the city main channel of the Forio Creek. The final model has 9 open or covered channel cells, representing the main stream crossing the city. There are 36 other cells representing minor drainage storm drains and, in addition to these, the model has 132 surface cells. The final division of the basin into cells has been written as a topological scheme, which defines the relative positions between each two cells and defines the hydraulic relations linking these cells. Figure 4 shows the watershed subdivision into cells. The model calibration was held in a non-conventional way. There were no formal measures for the observed flooding over streets and consequent superficial flows. Therefore, considering the rainfall design as the critical reference event to proceed with the calibration process, the model was adjusted to represent the flooded areas and the relative severity of the flooding in these areas, accordingly to the information given by the municipality staff and population memory of flood records. This support was important to raise the model reliability.

Simulation scenarios

338 We proposed a set of simulation scenarios in the design phase, in order to assess the
339 different possibilities and to check which measures could enhance the final solution in terms of risk
340 reduction:

- 341 ▪ ALT.0 – BASELINE: represents the reference alternative to be compared with all the others.
342 The "ALT.0" simulation considered the current situation of Cittanova, without carrying out
343 any works. This may be a possible choice when protection works are too expensive and the
344 socioeconomic losses do not justify the investment.
- 345 ▪ ALT.1 – DETENTION PONDS: in this alternative, five squares and green areas of
346 Cittanova were converted into detention basins, in a multifunctional landscape approach
347 (that is, the flood storage function was added to original functions). The location of these
348 areas is shown in Figure 5.
- 349 ▪ ALT.2 – ON-SITE DETENTION TANKS: this alternative considers the construction of on-
350 site detention tanks with 3.6 m^3 per each 100 m^2 of rooftops
- 351 ▪ ALT.3 - ON-SITE DETENTION TANKS: this alternative considers the construction of on-
352 site detention tanks with 4.5 m^3 per each 100 m^2 of rooftops.
- 353 ▪ ALT.4 – This alternative joins ALT.1+ALT.2.
- 354 ▪ ALT.5 – OPENING OF FORIO CREEK: this alternative opens a reach of 300 m of the
355 underground watercourse running through Cittanova.
- 356 ▪ ALT.6 – This alternative assumes ALT.1 + ALT.2 + ALT.5.
- 357 ▪ ALT.7 – DAM CONSTRUCTION IN MONTE FOSSO: this alternative simulates a dam in
358 the Forio Creek, upstream of the town of Cittanova, with the objective of damping its
359 floods.
- 360 ▪ ALT.8 – This alternative assumes ALT.1 + ALT.3 + ALT.5.

361 Appendix 1 shows the results obtained in the format of flood maps.

362 Mapping flood risk

363 The main stakeholders involved in this case study set the final FRI indicators and their
364 weights. Therefore, regarding the flood properties only, the values of water depth and velocity
365 factor have been used and normalised, while regarding the consequences, the population,
366 importance of roads, economic activities and structures of particular interest, including cultural or
367 archaeological heritage and environmental assets, have been considered. Thus, the following risk
368 maps (Figure 6) were obtained for the following selected alternatives: ALT.0; ALT.2; ALT.7 and
369 ALT.8.

370 This study allowed us to identify the most fragile and risky areas of the city of Cittanova
371 and to understand how the main physical processes act, as well as their relative importance. In
372 addition, the different alternatives allowed the evaluation of different possibilities of reducing flood
373 risks at different levels. This study is able to support the decision-making regarding social and
374 economic drivers.

375 Indeed, in this case, important points are highlighted as follows:

- 376 ▪ The current situation shows the inefficiency of the drainage system to deal with floods.
- 377 ▪ By observing the results obtained with the single alternatives (using just one type of
378 measure at a time) acting in a distributed way over the watershed (ALT.1, ALT.2 and
379 ALT.3) and that obtained with the laminating dam (ALT.7), it was possible to say that urban
380 runoff plays a central role in the city's flooding. The dam controlled water levels in the
381 river, but the flood map still showed significant areas under water. On the other side, when
382 using larger on-site detention tanks (4.5 m³ per each 100 m² of rooftops - ALT.3), there was
383 a significant improvement in the results, with lower water levels in fewer restricted areas.
- 384 ▪ Comparing ALT.7 (dam) with ALT.5 (opening of 300 m of Forio Creek, which is currently
385 closed underground), we perceive that both actions work by mainly reducing floods in the
386 river.
- 387 ▪ The best result in terms of flood control comes from a combined set of actions, using green
388 areas and public squares as detention ponds and detentions tanks (ALT.4), on source control,

and a partial urban river restoration approach, by re-opening a reach of 300m of Forio Creek (ALT.8).

- In terms of reducing risks, however, ALT.2, ALT.4 and ALT.8 had similar results.

In the end, there was a strong correlation between the problems highlighted in the hydraulic modelling and the ones identified by the city population through the questionnaires previously described. This result showed how the involvement of the population is valuable in improving the model reliability in the calibration phase.

Conclusions

The process of urbanisation has changed the natural landscape and increased flooding problems in the city of Cittanova, in Reggio Calabria (Italy). In fact, due to the urbanisation process of the past recent years and the consequent soil sealing, it has become more difficult to manage floods and more valuable assets are now exposed to risks.

Using the support of mathematical models, and by combining a hydrodynamic model and a quantitative multi-criteria risk index (MODCEL + FRI), it was possible to assess flood hazards and urban vulnerabilities, and produce a huge amount of results which highlighted various options for urban risk mitigation. This framework produced a decision support tool that allowed the evaluation, identification and comparison of critical areas in terms of flood risks and flood levels. Subsequent to this, it was possible to evaluate flood risk scenarios associated with different flood control alternatives, and to support the strategic planning for flood risk mitigation for the city of Cittanova, which led to a combined perspective which considered both the hazard and its associated consequences.

This combined methodology can be used as a decision supporting tool to allow a quantitative comparison and ranking of critical areas. It is also useful in defining the hierarchy of different possible interventions and in the justification of public investment. It is interesting to note that it is also possible to compare quantitatively different scenarios for the same region, estimating

414 the impacts of future urban development, and thus providing planning recommendations,
415 considering the population safety as a primary objective.

416 In the case examined, the current drainage system is inefficient in managing flooding in the
417 city of Cittanova. The alternative solution concerning the construction of storage ponds in green
418 areas is very useful to achieve the objective of safeguarding the buildings, roads, railways and
419 especially public safety, with relatively low associated costs. This alternative solution can be further
420 complemented by two other actions that improve flood risk control:

421 (1) the opening of Forio Creek, bringing it back into the urban landscape, and offering it
422 more space to avoid the backwater effects on the storm drains; and

423 (2) the individual adaptation of the existing buildings by adding a detention tank to control
424 the runoff generated by rooftops.

425 This second action also shows the positive aspect of actively involving the population in
426 the proposed solution, which is a key element in upholding any solution over time. On the other
427 hand, these complementary actions imply a greater public investment in re-opening Forio Creek and
428 greater private investments in adapting the city housing. A strategy to implement this alternative
429 should be developed, matching municipal and private investment capacity. This is the proposed
430 next step to complement the research – to develop and introduce this framework – it will be
431 important to provide a quantitative measure to hierarchise investments, comparing the costs and
432 benefits of each proposition, and verifying if the chosen alternative is feasible.

433

434 **References**

- 435 Abily, M., Duluc, C.M., Faes, J.B. and Gourbesville, P. (2013). “Performance assessment of
436 modelling tools for high resolution runoff simulation over an industrial site.” *Journal of*
437 *Hydroinformatics*, 15 (4), 1296–1311.
- 438 Ahiablame, L. M., Engel, B. A. and Chaubey, I. (2012). Effectiveness of Low Impact Development
439 Practices: Literature Review and Suggestions for Future Research. Water, Air & Soil
440 Pollution, Vol. 223, n.7. Netherlands.
- 441 Ahiablame, L.M. and Shakya, R. (2016). Modeling flood reduction effects of low impact
442 development at a watershed scale. *Journal of environmental management*, v. 171, p. 81-91,
443 2016.
- 444 Andersson E. (2006). “Urban Landscapes and Sustainable Cities.” *Ecology and Society*, 11 (1).
- 445 Argue, J.R., Ed. (2004). WSUD: Basic Procedures for ‘Source Control’ of Stormwater – a
446 Handbook for Australian practice. Adelaide: Urban Water Resources Centre, University of
447 South Australia.
- 448 Avila H., Avila L. and Sisa A. (2016) “Dispersed Storage as Stormwater Runoff Control in
449 Consolidated Urban Watersheds with Flash Flood Risk” *Journal of Water Resources*
450 *Planning and Management*, 142 (12)
- 451 Balica S. F., Douben N. and Wright N. G. (2009). “Flood vulnerability indices at varying spatial
452 scales.” *Water Science & Technology*, 60 (10), 2571–2580.
- 453 Barbaro G., Scionti F., Foti G. and Tripodi G. (2015). “La pianificazione degli interventi di
454 minimizzazione del rischio: analisi idrologico-idraulica e proposta innovativa e sostenibile per
455 le aree inondabili del torrente Forio di Cittanova” *III Convegno Italiano sulla riqualificazione*
456 *fluviale*, Reggio Calabria.
- 457 Barbedo, J., Miguez, M.G., Van Der Horst, D., Carneiro, P.R.F., Amis, P. and Ioris, A. (2015).
458 Policy dimensions of land-use change in peri-urban floodplains: the case of Paraty. *Ecology*

459 *and Society: a journal of integrative science for resilience and sustainability*, v. 20, p. 20(1):
460 5.

461 Barbosa, A.E., Fernandes, J. N. and David, L. M. (2012). Key issues for sustainable urban
462 stormwater management. In: Water Research. In Press, Corrected Proof, Available online 25
463 May 2012.

464 Barreto W., Vojinovic Z., Price R. and Solomatine D. (2010). “Multiobjective Evolutionary
465 Approach to Rehabilitation of Urban Drainage Systems” *Journal of Water Resources*
466 *Planning and Management*, 136 (5).

467 Blackmore J. and Plant R. (2008). “Risk and Resilience to Enhance Sustainability with Application
468 to Urban Water Systems “, *Journal of Water Resources Planning and Management*, 134 (3).

469 Brown, R.; Rogers, B.; Werbeloff, L. (2016). Moving toward Water Sensitive Cities.

470 Burian, S.J. and Edwards, F.G. (2002). “Historical Perspectives of Urban Drainage.” *Proceedings of*
471 *9th International Conference on Urban Drainage (ICUD)*, 8-13 September, Portland,
472 OR/USA, International Water Association (IWA).

473 Carlson, C., Barreteau, O., Kirshen, P., & Foltz, K. (2014). Storm water management as a public
474 good provision problem: survey to understand perspectives of low-impact development for
475 urban storm water management practices under climate change. *Journal of Water Resources*
476 *Planning and Management*, 141(6), 04014080.

477 Chocat, B., Ashley, R., Marsalek, J., Matos, M.R., Rauch, W., Schilling, W. and Urbonas , B.
478 (2007). Toward the Sustainable Management of Urban Storm-Water. *Indoor and Built*
479 *Environment*, 16 (3), 273-285.

480 Connelly, E.B., Thorisson, H., Valverde Jr., L.J. and Lambert J.H. (2016). Asset risk management
481 and resilience for flood control, hydropower, and waterways. *ASCE-ASME Journal of Risk*
482 *and Uncertainty in Engineering Systems, Part A: Civil Engineering*, v. 2, n. 4, p. 04016001,
483 2016.

484 Cunge, J.A., Holly Jr., F.M. and Verwey, A. (1980). *Practical Aspects of Computational River*
485 *Hydraulics*, Pitman Advanced Publishing Program. England.

486 Feldman, A.D. (2000). “Hydrologic Modeling Systems HEC-HMS Technical Reference Manual.”
487 *US Army Corps of Engineers*, Davis, CA, USA.

488 Fletcher, T.D., Shuster, W., Hunt, W. F., Ashley, R., Butler, D., Arthur, S., Trowsdale, S., Barraud,
489 S., Semadeni-Davies, A., Bertrand-Krajewski, J., Mikkelsen, P. S., Rivard, G., Uhl, M.,
490 Dagenais, D. and Viklander, M. (2015). SUDS, LID, BMPs, WSUD and more – The
491 evolution and application of terminology surrounding urban drainage. *Urban Water Journal*,
492 v. 12, n. 7, p. 525-542.

493 Giacomoni, M. H., & Joseph, J. (2017). Multi-Objective Evolutionary Optimization and Monte
494 Carlo Simulation for Placement of Low Impact Development in the Catchment Scale. *Journal*
495 *of Water Resources Planning and Management*, 143(9), 04017053.

496 Godschalk D.R. (2003). “Urban Hazard Mitigation: Creating Resilient Cities.” *Natural Hazards*
497 *Review*, 4 (3), 136–143.

498 Hossain, F., Beighley, E., Burian, S., Chen, J., Mitra A., Niyogi D., Pielke, R. and Wegner, D.
499 (2017). Review of Approaches and Recommendations for Improving Resilience of Water
500 Management Infrastructure: The Case for Large Dams. *Journal of Infrastructure Systems*, p.
501 02517001, 2017.

502 Jha A.K., Bloch R. and Lamond J. (2012). *Cities and Flooding. A Guide to Integrated Urban Flood*
503 *Risk Management for the 21st Century*, Washington, D.C.: The World Bank.

504 Johnstone, P. (2011). Water Sensitive Cities – Science-Policy Partnership. In: 12th International
505 Conference on Urban Drainage - ICUD, 10-15 September, Porto Alegre/Brazil. International
506 Water Association (IWA).

507 Kim, Y. and Han, M., (2007). “Rainfall-Storage-Drain (RSD) model for Runoff Control Rainwater
508 Tank System Design in Building Rooftop.” *Rainwater Research Center in Seoul National*
509 *University*.

510 Leandro, J., Chen, A.S., Djordjević S. and Savić D.A. (2009). “Comparison of 1D/1D and 1D/2D
511 Coupled (Sewer/Surface) Hydraulic Models for Urban Flood Simulation.” *Journal of*
512 *Hydraulic Engineering*, ASCE, 495–504.

513 Mascarenhas, F.C.B. and Miguez, M.G. (2002). “Urban Flood Control through a Mathematical Cell
514 Model.” *Water International*, 27 (2), 208–218.

515 Mascarenhas, F.C.B., Toda, K., Miguez, M.G. and Inoue, K. (2005). *Flood risk simulation*, WIT,
516 Southampton, Boston.

517 Mcanally, W.H., Wallen C.M., Sanborn, S.C. and Maak E.C. (2013). Composite risk assessment for
518 the Sacramento–San Joaquin delta levee system. *Journal of Water Resources Planning and*
519 *Management*, v. 140, n. 5, p. 734-743.

520 Mguni, P., Herslund, L. and Jensen, M.B. (2016). Sustainable urban drainage systems: examining
521 the potential for green infrastructure-based stormwater management for Sub-Saharan cities.
522 *Natural Hazards*, v. 82, n. 2, p. 241-257.

523 Miguez, M.G., Mascarenhas, F.C.B. and Veról, A.P. (2011). “A Matemactical Model for Urban
524 Flood Simulation and Integrated Flood Control Design.” *Proceedings of Acqua e Città 2011 -*
525 *4° Convegno Nazionale di Idraulica Urbana*, Venezia.

526 Miguez, M.G., Veról, A.P. and Carneiro, P.R.F. (2012). *Sustainable Drainage System: An*
527 *Integrated Approach, Combining Hydraulic Engineering Design, Urban Land Control and*
528 *River Revitalisation Aspects*. In *Drainage Systems*, Prof. Muhammad Salik Javaid (Ed.),
529 InTech.

530 Miguez, M.G. and Veról, A.P. (2016). *A catchment scale Integrated Flood Resilience Index to*
531 *support decision making in urban flood control design*. In *Environment and Planning B:*
532 *Planning and design*, SAGE.

533 Nardini, A. and Miguez, M.G. (2016). An Integrated Plan to Sustainably Enable the City of
534 Riohacha (Colombia) to Cope with Increasing Urban Flooding, while Improving Its
535 Environmental Setting. *Sustainability* (Basel), v. 8, p. 198-227.

536 Prasad, N., Ranghieri, F., Shah, F., Trohanis, Z., Kessler, E. and Sinha, R. (2009). *Climate Resilient*
537 *Cities. A Primer on Reducing Vulnerabilities to Disasters*. Washington, D.C.: The World
538 Bank.

539 Rossman, L.A. (2015). "Storm Water Management Model User's Manual Version 5.1." *United*
540 *States Environmental Protection Agency*, Cincinnati, OH, USA.

541 Scharffengerg, W.A. and Fleming, M.J. (2010). "Hydrologic Modeling Systems HEC-HMS User's
542 Manual, version 3.5." *US Army Corps of Engineers*, Davis, CA, USA.

543 US EPA – United States Environmental Protection Agency (2000). Low Impact Development – A
544 Literature Review. EPA-841-B-00-005. Washington, DC: Office of Water USA.

545 Vale, L. and Campanella T. (2005). *The Resilient City: How Modern Cities Recover From Disaster*.
546 New York, Oxford University Press.

547 Wang, C. H., & Blackmore, J. M. (2009). Resilience concepts for water resource systems. *Journal*
548 *of Water Resources Planning and Management*, 135(6), 528-536.

549 Walsh, C.J., Booth, D.B., Burns, M.J., Fletcher, T.D., Hale, R.L., Hoang, L.N., Livingston,
550 G., Rippy, M.A., Roy, A.H., Scoggins M. and Wallace A. (2016). Principles for urban
551 stormwater management to protect stream ecosystems. *Freshwater Science*, v. 35, n. 1, p. 398-
552 411, 2016.

553 Wong, T. and Brown, R. (2008). Transitioning to Water Sensitive Cities: Ensuring Resilience
554 through a new Hydro-Social Contract. In: 11th International Conference on Urban Drainage,
555 31 August-5 September, Edinburgh, UK. International Water Association (IWA).

556 Woods-Ballard, B., Kellagher, R., Martin, P., Bray, R. and Shaffer, P., (2007). The SUDS Manual.
557 CIRIA C697. London: CIRIA.

558 Woodward, M., Gouldby, B., Kapelan, Z., & Hames, D. (2013). Multiobjective optimization for
559 improved management of flood risk. *Journal of Water Resources Planning and Management*,
560 140(2), 201-215.

561 Zanobetti, D., Lorgeré, H., Preissman, A. and Cunge, J.A. (1970). “Mekong Delta Mathematical
562 Program Construction.” *Journal of the Waterways and Harbours Division*, ASCE, 96 (WW2),
563 181–199.

564 Zonensein, J., Miguez, M.G., de Magalhães, L.P.C., Valentin, M.G. and Mascarenhas, F.C.B.
565 (2008). Flood Risk Index as an Urban Management Tool. *Proceedings of 11th International*
566 *Conference on Urban Drainage*, Edinburgh, Scotland, UK.

567

568 **Captions**

569 Figure 1: schematic representation of a portion of a watershed divided into cells, showing different
570 interactions and flow patterns modelled by MODCEL.

571 Figure 2: pre-defined urban pattern introduced in a MODCEL simulation.

572 Figure 3: the town of Cittanova and its urban tissue appear on the left; Vacale watershed, with Forio
573 passing through the centre of the city, appears on the right.

574 Figure 4: aerial view and plan cell division.

575 Figure 5: location of the detention ponds.

576 Figure 6: Flood risk maps for alternatives ALT.0, ALT.2, ALT.7 and ALT.8.

577 Table 1: design rainfall.


578 Appendix 1: flood maps results for the simulated alternatives using a return period of 50 years.


579 **Tables**


580 Table 1: design rainfall.



Time [minutes]	Total rainfall [mm]	Average intensity [mm/h]	Incremental rainfall in 10 minute time step [mm]
10	37.8	226.8	37.8
20	49.9	149.7	12.1
30	58.8	117.6	8.9

581

















ASCE Authorship, Originality, and Copyright Transfer Agreement

Publication Title: Journal of Water Resources, Planning and Management

Manuscript Title: An Integrated Methodology for urban flood risk mitigation: the case study of Cittanova (Italy)

Author(s) – Names, postal addresses, and e-mail addresses of all authors

Fabio Scionti, Via Graziella località Feo di Vito, 89122 Reggio Calabria (Italy). fascipama@tiscali.it

Marcelo Gomes Miguez, Av. Athos da Silveira Ramos, 149, CT, I-206 Cidade Universitária Rio de Janeiro (Brasil). marcelomiguez@poli.uerj.br

Giuseppe Barbaro, Via Graziella località Feo di Vito, 89122 Reggio Calabria (Italy). giuseppe.barbaro@unirc.it

Matheus Martins De Sousa, Rua Paulo Emílio Barbosa, 495, 1A, CE 71C, 106 Cidade Universitária - Parque Tecnológico da UFRJ Rio de Janeiro (Brasil). matheus@equifluxo.com.br

Giandomenico Foti, Via Graziella località Feo di Vito, 89122 Reggio Calabria (Italy). giandomenico.foti@unirc.it

CATCHING WATER WITH THE FLOOD LOC. Feo di Vito, 89122 Reggio Calabria

I. Authorship Responsibility

To protect the integrity of authorship, only people who have significantly contributed to the research or project and manuscript preparation shall be listed as coauthors. The corresponding author attests to the fact that anyone named as a coauthor has seen the final version of the manuscript and has agreed to its submission for publication. Deceased persons who meet the criteria for coauthorship shall be included, with a footnote reporting date of death. No fictitious name shall be given as an author or coauthor. An author who submits a manuscript for publication accepts responsibility for having properly included all, and only, qualified coauthors.

I, the corresponding author, confirm that the authors listed on the manuscript are aware of their authorship status and qualify to be authors on the manuscript according to the guidelines above.

Giuseppe Barbaro

Print Name

Signature

Date

10/4/2017

II. Originality of Content

ASCE respects the copyright ownership of other publishers. ASCE requires authors to obtain permission from the copyright holder to reproduce any material that (1) they did not create themselves and/or (2) has been previously published, to include the authors' own work for which copyright was transferred to an entity other than ASCE. Each author has a responsibility to identify materials that require permission by including a citation in the figure or table caption or in extracted text. Materials re-used from an open access repository or in the public domain must still include a citation and URL, if applicable. At the time of submission, authors must provide verification that the copyright owner will permit re-use by a commercial publisher in print and electronic forms with worldwide distribution. For Conference Proceeding manuscripts submitted through the ASCE online submission system, authors are asked to verify that they have permission to re-use content where applicable. Written permissions are not required at submission but must be provided to ASCE if requested. Regardless of acceptance, no manuscript or part of a manuscript will be published by ASCE without proper verification of all necessary permissions to re-use. ASCE accepts no responsibility for verifying permissions provided by the author. Any breach of copyright will result in retraction of the published manuscript.

I, the corresponding author, confirm that all of the content, figures (drawings, charts, photographs, etc.), and tables in the submitted work are either original work created by the authors listed on the manuscript or work for which permission to re-use has been obtained from the creator. For any figures, tables, or text blocks exceeding 100 words from a journal article or 500 words from a book, written permission from the copyright holder has been obtained and supplied with the submission.

Giuseppe Barbaro

Print name

Signature

Date

10/4/2017

III. Copyright Transfer

ASCE requires that authors or their agents assign copyright to ASCE for all original content published by ASCE. The author(s) warrant(s) that the above-cited manuscript is the original work of the author(s) and has never been published in its present form.

The undersigned, with the consent of all authors, hereby transfers, to the extent that there is copyright to be transferred, the exclusive copyright interest in the above-cited manuscript (subsequently called the "work") in this and all subsequent editions of the work (to include closures and errata), and in derivatives, translations, or ancillaries, in English and in foreign translations, in all formats and media of expression now known or later developed, including electronic, to the American Society of Civil Engineers subject to the following:

- The undersigned author and all coauthors retain the right to revise, adapt, prepare derivative works, present orally, or distribute the work, provided that all such use is for the personal noncommercial benefit of the author(s) and is consistent with any prior contractual agreement between the undersigned and/or coauthors and their employer(s).
- No proprietary right other than copyright is claimed by ASCE.
- If the manuscript is not accepted for publication by ASCE or is withdrawn by the author prior to publication (online or in print), or if the author opts for open-access publishing during production (journals only), this transfer will be null and void.
- Authors may post a PDF of the ASCE-published version of their work on their employers' **Intranet** with password protection. The following statement must appear with the work: "This material may be downloaded for personal use only. Any other use requires prior permission of the American Society of Civil Engineers."
- Authors may post the **final draft** of their work on open, unrestricted Internet sites or deposit it in an institutional repository when the draft contains a link to the published version at www.ascelibrary.org. "Final draft" means the version submitted to ASCE after peer review and prior to copyediting or other ASCE production activities; it does not include the copyedited version, the page proof, a PDF, or full-text HTML of the published version.

Exceptions to the Copyright Transfer policy exist in the following circumstances. Check the appropriate box below to indicate whether you are claiming an exception:

☐ **U.S. GOVERNMENT EMPLOYEES:** Work prepared by U.S. Government employees in their official capacities is not subject to copyright in the United States. Such authors must place their work in the public domain, meaning that it can be freely copied, republished, or redistributed. In order for the work to be placed in the public domain, ALL AUTHORS must be official U.S. Government employees. If at least one author is not a U.S. Government employee, copyright must be transferred to ASCE by that author.

☐ **CROWN GOVERNMENT COPYRIGHT:** Whereby a work is prepared by officers of the Crown Government in their official capacities, the Crown Government reserves its own copyright under national law. If ALL AUTHORS on the manuscript are Crown Government employees, copyright cannot be transferred to ASCE; however, ASCE is given the following nonexclusive rights: (1) to use, print, and/or publish in any language and any format, print and electronic, the above-mentioned work or any part thereof, provided that the name of the author and the Crown Government affiliation is clearly indicated; (2) to grant the same rights to others to print or publish the work; and (3) to collect royalty fees. ALL AUTHORS must be official Crown Government employees in order to claim this exemption in its entirety. If at least one author is not a Crown Government employee, copyright must be transferred to ASCE by that author.


☐ **WORK-FOR-HIRE:** Privately employed authors who have prepared works in their official capacity as employees must also transfer copyright to ASCE; however, their employer retains the rights to revise, adapt, prepare derivative works, publish, reprint, reproduce, and distribute the work provided that such use is for the promotion of its business enterprise and does not imply the endorsement of ASCE. In this instance, an authorized agent from the authors' employer must sign the form below.

☐ **U.S. GOVERNMENT CONTRACTORS:** Work prepared by authors under a contract for the U.S. Government (e.g., U.S. Government labs) may or may not be subject to copyright transfer. Authors must refer to their contractor agreement. For works that qualify as U.S. Government works by a contractor, ASCE acknowledges that the U.S. Government retains a nonexclusive, paid-up, irrevocable, worldwide license to publish or reproduce this work for U.S. Government purposes only. This policy DOES NOT apply to work created with U.S. Government grants.

I, the corresponding author, acting with consent of all authors listed on the manuscript, hereby transfer copyright or claim exemption to transfer copyright of the work as indicated above to the American Society of Civil Engineers.

Giuseppe Barbaro

Print Name of Author or Agent



Signature of Author or Agent

6/4/2017

Date

More information regarding the policies of ASCE can be found at <http://www.asce.org/authorsandeditors>.

Ref.: Ms. No. WRENG-2813R2

“An Integrated Methodology for urban flood risk mitigation: the case study of Cittanova (Italy)”

Authors: Fabio Scionti; Marcelo Gomes Miguez; Giuseppe Barbaro; Matheus Martins De Sousa; Giandomenico Foti; Caterina Canale

Author's Responses to EDITOR:

Editor Comments:

Editor: Based on the reviews, it is recommended that the author should revise and resubmit the manuscript. The author is encouraged to review the past JWRM publications on this subject and to take the reviewer comments into consideration in improving the paper

Author's response: We revised the past JWRM publications and we found it very useful, improving our literature review. Four (4) new references from the JWRM were added to the references list, in a total of eight (8) citations, as seen below:

Avila H., Avila L. and Sisa A. (2016) “Dispersed Storage as Stormwater Runoff Control in Consolidated Urban Watersheds with Flash Flood Risk” **Journal of Water Resources Planning and Management**, 142 (12)

Barreto W., Vojinovic Z., Price R. and Solomatine D. (2010). “Multiobjective Evolutionary Approach to Rehabilitation of Urban Drainage Systems” **Journal of Water Resources Planning and Management**, 136 (5).

Blackmore J. and Plant R. (2008). “Risk and Resilience to Enhance Sustainability with Application to Urban Water Systems “, *Journal of Water Resources Planning and Management*, 134 (3).

Carlson, C., Barreteau, O., Kirshen, P., & Foltz, K. (2014). Storm water management as a public good provision problem: survey to understand perspectives of low-impact development for urban storm water management practices under climate change. **Journal of Water Resources Planning and Management**, 141(6), 04014080.

Giacomoni, M. H., & Joseph, J. (2017). Multi-Objective Evolutionary Optimization and Monte Carlo Simulation for Placement of Low Impact Development in the Catchment Scale. **Journal of Water Resources Planning and Management**, 143(9), 04017053.

Mcanally, W.H., Wallen C.M., Sanborn, S.C. and Maak E.C. (2013).Composite risk assessment for the Sacramento–San Joaquin delta levee system. **Journal of Water Resources Planning and Management**, v. 140, n. 5, p. 734-743.

Wang, C. H., & Blackmore, J. M. (2009). Resilience concepts for water resource systems. **Journal of Water Resources Planning and Management**, 135(6), 528-536.

Woodward, M., Gouldby, B., Kapelan, Z., & Hames, D. (2013). Multiobjective optimization for improved management of flood risk. **Journal of Water Resources Planning and Management**, 140(2), 201-215.

Reviewers' comments:

Editor: I apologize for the delay with this review. A number of reviewers were either unresponsive or unable to complete their reviews. However, I have checked authors' responses to previous review comments and have found them to be satisfactory, with the possible exception of one remaining concern, noted by Reviewer #1 below.

Author's response: Reviewer #1 concern will be answered in the sequence.

I also note that the paper is over-length. Technical papers should be 10,000 word-equivalents or less, including the word-equivalent space of tables and figures. For example, a printed journal page is about 1,200 words, and thus a large figure or table using 1/2 page would be 600 word-equivalents. Alternatively, double-spaced manuscripts meeting this requirement are usually about 30-35 pages (including tables and figures), and this manuscript exceeds 40 pages, including figures and tables. Authors are asked to consider omitting some detailed results, or else including them as Supplemental Information (especially figures that have been designated as part of an Appendix). Also, Figures 7-10 might be combined as one or two multi-panel figures.

Author's response: the text as a whole was thoroughly revised and reduced in almost 10%. We apologize by the length of the final paper, but it is important to note that we started with a manuscript matching the rules, but its size increased to fulfil the Reviewers comments along the revision process. We also eliminated Figure 4 and we combined figures 7, 8, 9 and 10 in only one figure. All the main figures (except for the appendix) are now occupying about 3 pages. The text from the introduction to the conclusion has now 4948 words, even considering that we introduced 4 new references. The total manuscript length, also considering title, author's names, abstract and references has 7008 words. In terms of number of pages, the manuscript presents about 30 pages, double-spaced, including all figures and tables.

Reviewer #1: The authors answered satisfactorily to two of the three points addressed in the previous reviews.

About the third point, the one about the need of performing several hydraulic analysis in order to predict the hydraulic risk for fixed time return periods in all the basin area, we must observe the following:

The criterion used by the authors to design the input hydrograph guarantees that the most dangerous event, corresponding to a time period of 10 minutes, is attained only for the smaller sub-basins with smaller concentration time. For the

closure sections of larger sub-basins and of the entire basin, it is well-known that hydraulic effect of the input hydrograph depends not only by the volume of the hydrograph, but also by its shape. According to the proposed procedure the shape of the input hydrograph (assuming very small time intervals with constant rain intensity) has an initial discontinuity and then asymptotically decreases. Is this a dangerous shape? There is some reference in literature? The authors should address this point before publication.

Author`s response: We understood the Reviewer #1 concerns. Our text was revised to address his comment and it now reads as:

“The design rainfall was built considering incremental rainfall blocks of ten minutes each. The duration of ten minutes was considered as the minimal critical time step to evaluate minor drainage behaviour. That is, when considering blocks of ten minutes, the maximum intensity obtained for this duration is the critical rainfall to curbs and inlets in the local scale. On the other hand, completing the total design hyetograph until reaching the concentration time of 30 minutes, the watershed is also subjected to its critical rainfall event in terms of total volume. Therefore, the total rainfall and the intensity were calculated every 10 minutes, up to 30 minutes, as presented in Table 1. Note that the second block is the result of the total rainfall for 20 minutes minus the total rainfall for the first 10 minutes. Similarly, the third block refers to the total rainfall of 30 minutes minus the total rainfall of 20 minutes. This approach allowed to simulate the critical rainfall intensity in the watershed scale (represented by the average value of the three blocks), as well as the critical rainfall intensity in the local scale (given by the rainfall intensity of the first block). It is important to remind that the resulting hydraulic effects on the watershed responses depend not only on the volume of the hydrograph, but also on its shape. This complementary aspect, however, was not explored in this research.